PROPOSED RESIDENTIAL HOUSE ON PLOT LR NO

FOR

JEREMIAH MUSOMBA MUINDE

IN

KATUANYAGA, EMBU COUNTY

BILLS OF QUANTITIES

Kerali
CONSTRUCTION COMPANY LTD

CONTENTS

* Bills of Quantities

CONTRACTORS

Kerali Construction Company
P.O. Box 8946 - 00200
Nairobi

26/2/2025

FEBRUARY, 2025

Item	Description	Unit	Qty	Rate	Amount
	SECTION 2 - MAIN HOUSE				
	ELEMENT NO. 1				
	SUBSTRUCTURES (PROVISIONAL)				
	Excavations including trimming sides and bottoms of excavations; maintaining and supporting sides; and keeping free from water, mud and fallen material; with and including destruction of termites nests within site of works,take out and destroy queens, impregnate holes and tunnels with insecticide and fill voids with approved material				
	Excavation				
A	Clear the site of unwanted shrubes, bushes and trash and dispose off or burn arising thereof as instructed	Sm	220.00	50.00	11,000.00
B	Excavations to remove vegetable top soil average depth 200mm and cart away	Sm	220.00	200.00	44,000.00
C	Excavate trench for foundation not exceeding 1.50 metres deep, starting from reduced levels	Cm	95.00	350.00	33,250.00
D	Extra over excavations for excavating in soft rock	Cm	1.00	1,300.00	1,300.00
E	Extra over excavations for excavating in hard rock	Cm	1.00	1,900.00	1,900.00
	Disposal				
F	Return, fill and ram selected excavated material around foundations.	Cm	28.50	150.00	4,275.00
G	Load, wheel and deposit surplus excavated material away from site	Cm	66.50	350.00	23,275.00
	Hardcore or other approved filling, as described				
H	300mm Thick well compacted hardcore filling blinded with 50,mm thick quarry dust layer to receive surface bed	Sm	190.00	850.00	161,500.00
	Anti - termite to treatment				
I	Chemical anti-termite treatment (GLADIATOR), executed complete by an approved specialist under a ten-year guarantee,to surfaces of hardcore	Sm	190.00	150.00	28,500.00
	Carried to Collection				**309,000.00**

Item	Description	Unit	Qty	Rate	Amount
	Damp-proof membrane				
A	1000 Gauge polythene or other equal and approved damp-proof membrane, laid over blinded hardcore (measured separately) with 300mm side and end laps (measured nett-allow for laps) measurement including retainer walls waterproofing	Sm	220.00	150.00	33,000.00
	Mesh fabric reinforcement to B.S 4483 and setting in concrete with 300mm side and end laps (measured nett-allow for laps).				
B	Fabric ref. A142 in surface in surface bed	Sm	220.00	400.00	88,000.00
	Plain concrete class 15 in:				
C	50mm Blinding under foundations.	Sm	55.00	500.00	27,500.00
	Vibrated reinforced concrete class (20) as described, in:-				
D	Strip footing	Cm	10.00	13,000.00	130,000.00
E	150mm Thick slab	Sm	220.00	1,950.00	429,000.00
	Reinforcement, as described:-[PROVISIONAL]				
	High yield square twisted reinforcement to BS 4461				
F	10mm Diameter bars - Strip Fdn	Kg	270.00	190.00	51,300.00
G	8mm Diameter bars - Strip fdn, suspended slab, Cols	Kg	190.00	190.00	36,100.00
	Sawn formwork as described to:-				
H	Vertical sides of strip footing	Sm	75.00	550.00	41,250.00
I	Edge of rises over 75mm but not exceeding 150mm girth	Lm	75.00	100.00	7,500.00
	Walling				
	Natural hard approved quarry stone walling with a crushing strength of 7.5 N/mm²; walling bedded and jointed in cement and sand (1:4) mortar, reinforcement with and including 25mm wide x 20 gauge hoop iron at every alternate course as described in:				
J	200mm Thick walling	Sm	130.00	1,950.00	253,500.00
	Carried to Collection				**1,097,150.00**

Item	Description	Unit	Qty	Rate	Amount
	Damp-proof courses, as described, to walls				
A	200mm Wide	Lm	121.00	150.00	18,150.00
	Two coat external render cement sand (1:4) with a woodfloat				
B	12mm Thick to plinths	Sm	50.00	450.00	22,500.00
C	3 coats of Bituminous paint to rendered plinths	Sm	50.00	400.00	20,000.00
	Carried to Collection				**60,650.00**
	COLLECTION				
	From Page 2/1				309,000.00
	From Page 2/2				1,097,150.00
	From Page 2/3 above				60,650.00
	ELEMENT NO. 1 SUBSTRUCTURES **Carried to Main Summary**				**1,466,800.00**

Item	Description	Unit	Qty	Rate	Amount
	SECTION 2 - MAIN HOUSE				
	ELEMENT NO. 2				
	REINFORCED CONCRETE FRAME				
	Vibrated reinforced concrete class 20, as described in;-				
A	Beams and Columns	Cm	6.00	13,000.00	78,000.00
	High yield square twisted reinforcement to BS 4461				
B	12mm Diameter bars	Kg	310.00	190.00	58,900.00
C	10mm Diameter bars	Kg	130.00	190.00	24,700.00
D	8mm Diameter bars	Kg	250.00	190.00	47,500.00
	Sawn formwork, as described, to:-				
E	Sides of beams and columns	Sm	110.00	550.00	60,500.00
	ELEMENT NO. 2 **Carried to the**				
	REINFORCED CONCRETE WORK **Main Summary**				**269,600.00**

Item	Description	Unit	Qty	Rate	Amount
	SECTION 2 - MAIN HOUSE				
	ELEMENT NO. 3				
	WALLING				
	External Walling				
	Natural hard machine cut Thika stone from an approved quarry with a crushing strength of 7.5 N/mm²; walling bedded and jointed in cement and sand (1:4) mortar; reinforcement with and including 25mm wide x 20 gauge hoop iron at every alternate course as described in;				
A	200mm thick walling externally	Sm	140.00	1,600.00	224,000.00
	Internal Walling				
	Natural hard machine cut Thika stone from an approved quarry with a crushing strength of 7.5 N/mm²; walling bedded and jointed in cement and sand (1:4) mortar; reinforcement with and including 25mm wide x 20 gauge hoop iron at every alternate course as described in;				
B	200mm Thick walling	Sm	108.00	1,600.00	172,800.00
	ELEMENT NO. 3 WALLING **Carried to Main summary**				**396,800.00**

Item	Description	Unit	Qty	Rate	Amount
	SECTION 2 - MAIN HOUSE				
	ELEMENT NO. 4				
	ROOF CONSTRUCTION				
	Structural Timber Roof Construction				
	The following roof trusses in Celcured sawn cypress: maximum spans 11.80metres; hoisting and fixing up to 7.0 metres above ground level; all jointing to be carried out with the aid of a full size bolting template : including splice plates and all necessary fixing accesories to Structural Engineer's satisfaction.				
A	100 x 50mm Normal Rafters	Lm	270.00	300.00	81,000.00
B	100 x 50mm Hip rafters and Valley rafters	Lm	200.00	300.00	60,000.00
C	100 x 50mm Comon Rafters	Lm	350.00	300.00	105,000.00
D	100 x 50mm King post	Lm	75.00	300.00	22,500.00
E	100 x 50mm Ties and struts	Lm	260.00	300.00	78,000.00
F	100 x 50mm Tie beam	Lm	100.00	300.00	30,000.00
G	100 x 50mm Wallplate	Lm	120.00	300.00	36,000.00
H	100 x 50mm Battens/Purlins.	Lm	160.00	300.00	48,000.00
I	40 x 20mm ridge piece	Lm	45.00	190.00	8,550.00
	Versatile roofing sheets Gauge 28 on 30 degree slope or equal and approved with a 50 years warranty, : fixed and secured with and including approved self-tapping screws : on and including 40 x 40mm battens at 300 centres (minimum) : fixed strictly in accordance with manufacturer's instruction manual and to Architect's approval : as described :-				
J	Roof covering not exceeding 30 degrees from the horizontal including all necessary fixtures	Sm	255.00	1,900.00	484,500.00
K	Ridge or hip cover to match	Lm	130.00	950.00	123,500.00
L	Labour raking cutting roofing cover along valleys and hips	Lm	60.00	130.00	7,800.00
	Carried to Collection				**1,084,850.00**

Item	Description	Unit	Qty	Rate	Amount
	Wrot Softwood; treated cypress or equal and approved				
A	Moulded fascia board cover : 290mm girth : to approval	Lm	75.00	850.00	63,750.00
	Wrot cypress Eaves boarding				
B	Heavy gauge PVC ceiling fixed onto timber brandering or supporting 50x50mm timber frame; including all necessary tools and respective accessories	Sm	44.00	1,260.00	55,440.00
	Rainwater goods; (ALL PROVISIONAL)				
	UPVC gutters, down pipes and fittings other equal and approved; as required				
C	140mm PVC gutter including joints & all accessories in running length fixed to outside of fascia board with and including brackets at fascia centres	Lm	75.00	1,100.00	82,500.00
D	110mm Diameter UPVC downpipe fixed with and including holderbats plugged and screwed to walls	Lm	21.00	1,050.00	22,050.00
E	Ditto for outlet in gutter	No	6.00	900.00	5,400.00
F	Extra for swanneck offset in pipe diameter	No	6.00	900.00	5,400.00
G	Extra for shoe in pipe diameter	No	6.00	900.00	5,400.00
	Carried to Collection				**239,940.00**
	COLLECTION				
	Brought Forward from page 2/6				1,084,850.00
	Brought Forward from page 2/7				239,940.00
	ELEMENT NO. 4 **Carried to**		**Kshs**		**1,324,790.00**
	ROOF CONSTRUCTION **Main summary**				

Item	Description	Unit	Qty	Rate	Amount
	SECTION 2 - MAIN HOUSE				
	ELEMENT NO. 5				
	EXTERNAL FINISHES				
	Floor finishes				
	Cement and sand (1:3) screeds, backings, beds etc				
A	30mm Thick bed finished to receive ceramic floor tiles (m.s)	Sm	42.00	470.00	19,740.00
	Saj Ceramic floor tiling				
	Provide a prime cost rate of [Kshs 1700.00/sm] for supply & fixing of Saj ceramic floor tiles (tenderer to add the cost of collection from the Supplier's warehouses within Nairobi area, delivery, grouting, adhesive, spaces and all other materials and laying to completion) as selected by the Architect: take delivery and fix only saj ceramic tiles to floor on prepared screed (m.s) with proprietary adhesive; jointed and pointed in matching coloured proprietary grouting: including pvc spacers and expansion joint as necessary: all to Architect's approval.				
B	300x300x6mm	Sm	42.00	1,700.00	71,400.00
C	100x25mm tile skirting	Lm	15.00	170.00	2,550.00
	Wall finishes				
	15 mm cement and sand (1:3) render,finished with woodfloat, allow for anticrack mechanism including plastering to masonry and concrete surfaces as work proceeds in tight spaces less than one square metre on plan:-				
D	Concrete/masonry surfaces to receive weatherguard finish (m.s.) externally	Sm	160.00	465.00	74,400.00
	Prepare and apply one undercoat and two finishing coats first quality exterior quality weatherguard paint or any other similar and approved paint to:				
E	Rendered walls, columns beams and reveals of openings	Sm	160.00	450.00	72,000.00
	Carried to Collection				**240,090.00**

Item	Description	Unit	Qty	Rate	Amount
	Ceiling finishes				
	PVC heavy gauge ceiling with and including 50x50mm cypress bracings : fixed with countersunk screw;				
A	12mm thick; horizontal	Sm	42.00	1,260.00	52,920.00
B	25 x 100mm high matching cornice	Lm	30.00	150.00	4,500.00
	Carried to Collection				**57,420.00**
	COLLECTION				
	From Page 2/8				240,090.00
	From Page 2/9				57,420.00
	ELEMENT NO. 5 EXTERNAL FINISHES **Carried to Main summary**				**297,510.00**

Item	Description	Unit	Qty	Rate	Amount
	SECTION 2 - MAIN HOUSE				
	ELEMENT NO. 6				
	INTERNAL FINISHES				
	Floor Finishes				
	Cement and sand (1:3) screeds, backings, beds etc				
A	25mm Thick bed finished to receive Ceramic floor tiles (measured separately)	Sm	165.00	470.00	77,550.00
	Ceramic floor tiling				
	Provide a prime cost rate of [Kshs 1700.00/sm] for supply & fixing of Saj ceramic floor tiles (tenderer to add the cost of collection from the Supplier's warehouses within Nairobi area, delivery, grouting, adhesive, spaces and all other materials and laying to completion) as selected by the Architect: take delivery and fix only saj ceramic tiles to floor on prepared screed (m.s) with proprietary adhesive; jointed and pointed in matching coloured proprietary grouting: including pvc spacers and expansion joint as necessary: all to Architect's approval.				
B	300x300x6mm	Sm	165.00	1,700.00	280,500.00
C	100x25mm tile skirting	Lm	160.00	170.00	27,200.00
	Wall finishes				
	12mm (minimum) two coat lime plaster complete with wire gauze anti-crack mechanism at the intersection of masonry walling and concrete beams and service ducts; conduits as described to:-				
D	Concrete masonry surfaces internally	Sm	400.00	465.00	186,000.00
	Cement and sand (1:4) backings etc				
E	12mm Thick backing finished to receive ceramic wall tiles (measured separately)	Sm	40.00	465.00	18,600.00
	Ceramic wall tiling				
	Provide a prime cost rate of [Kshs 1600/sm] for supply & fixing of ceramic wall tiles (tenderer to add the cost of collection from the Supplier's warehouses delivery, grouting, adhesive, spaces and all other materials and laying to completion) as selected by the Architect: take delivery and fix only ceramic tiles to walls on prepared backing (m.s) with proprietary adhesive; jointed and pointed in matching coloured proprietary grouting: including pvc spacers and expansion joint as necessary: all to Architect's approval.				
F	300x250x6mm To Bathrooms, kitchen, cloak rooms	Sm	40.00	1,600.00	64,000.00
	Carried to Collection				**653,850.00**

Item	Description	Unit	Qty	Rate	Amount
	Painting and decorating				
	Prepare and apply three coats first quality silk vinyl emulsion paint on:-				
A	Plastered walls internally	Sm	400.00	450.00	180,000.00
	Ceiling finishes				
	PVC heavy gauge ceiling with and including 50x50mm cypress bracings : fixed with countersunk screw;				
B	12mm thick; horizontal	Sm	165.00	1,260.00	207,900.00
C	25 x 100mm high matching cornice	Lm	180.00	150.00	27,000.00
D	Extra over celotex ceiling for forming removable access trap door; size 600x600mm	No	2.00	1,680.00	3,360.00
	Carried to Collection				**418,260.00**
	COLLECTION				
	From Page 2/10				653,850.00
	From Page 2/11				418,260.00
	ELEMENT NO. 6 INTERNAL FINISHES **Carried to Main summary**				**1,072,110.00**

Item	Description	Unit	Qty	Rate	Amount
	SECTION 2 - MAIN HOUSE				
	ELEMENT NO. 7				
	WINDOWS				
	Window cill				
A	100 x 25mm Thick Precast concrete window cills once rebated and throated; laid and jointed in cement and sand (1:3) mortar including mastic seal for water tightening to approval	Lm	25.00	450.00	11,250.00
	Steel Casement windows				
	Supply, assemble and fix the following purpose made 25 x 4mm Z-section steel casement windows with and including 25 x 4mm mild steel flats same vertical and horizontal intervals of 250mm both ways as mullions,12X4mm bars at 120mm centres both ways as as burglar proof at openable sections only complete with fixing lugs; hooded insect mesh to permanent ventilations, including all necessary cutting, and ironmongery as supplied by 'Kensmetal' or equivalent including touch up primer in grey oxide primer.				
B	Window overall size 2000 x 2400 mm high	No	3.00	24,192.00	72,576.00
C	Window overall size 2000 x 1800 mm high	No	5.00	18,144.00	90,720.00
D	Window overall size 800 x 900 mm high	No	3.00	3,628.80	10,886.40
E	Window overall size 400 x 2400 mm high	No	1.00	4,838.40	4,838.40
	Carried to Collection				**190,270.80**

Item	Description	Unit	Qty	Rate	Amount
	Glazing				
	Supply and fix the following in metal putty				
A	4mm thick One-way tinted glass in panes 0.50 to 1.00 sm	Sm	34.00	2,700.00	91,800.00
B	Ditto but obscured glass in panes 0.1 to 0.5 sm	Sm	2.00	2,500.00	5,000.00
	Prepare and apply two undercoats and one gloss finishing coat enamel paint to metalwork				
C	Steel casement window; General surfaces externally (Measured both sides)	Sm	72.00	380.00	27,360.00
	Curtain tracks				
D	Supply and installation of wrot iron curtain rods; 25mm diameter	Lm	25.00	2,500.00	62,500.00
	Finishing to reveals				
	15 mm cement and sand (1:3) render, finished with woodfloat to:-				
E	Concrete or masonry surfaces externally	Sm	10.00	465.00	4,650.00
	12mm (minimum) two coat lime plaster as described to				
F	Concrete or masonry surfaces internally	Sm	10.00	465.00	4,650.00
	Prepare the surface (include skimming) and apply two undercoats and one finishing coat first quality silk vinyl emulsion paint on:-				
G	Plastered walls internally	Sm	10.00	450.00	4,500.00
	Prepare and apply three coats first silk vinyl quality emulsion paint on:-				
H	Rendered surfaces externally	Sm	10.00	450.00	4,500.00
				Carried to Collection	**204,960.00**
	COLLECTION				
	From Page 2/12				190,270.80
	From Page 2/13 above				204,960.00
	ELEMENT NO. 7 WINDOWS **Total Carried to Summary**				**395,230.80**

Item	Description	Unit	Qty	Rate	Amount
	SECTION 2 - MAIN HOUSE				
	ELEMENT NO 8				
	DOORS				
	Mild steel casement door; 25x25x2mm RHS outer frames and infilled with 25x25x2mm RHS members. 25x2mm thick Zed and Tee sections to architects detail and approval; including permanent ventilators comprising 'T' bar, gauze and metal hood; complete with all necessary fittings				
A	Overall size 1500 x 2400mm high	No	1.00	34,200.00	34,200.00
B	Door overall size 1300x2400	No	3.00	29,640.00	88,920.00
C	Door overall size 900x2400	No	2.00	20,520.00	41,040.00
	In Wrought Cypress				
D	50 x 20mm Architrave with two labours, plugged	Lm	63.00	210.00	13,230.00
E	50 x 20mm Quadrant with two labours, plugged	Lm	81.00	210.00	17,010.00
F	50 x 100mm Frame with two labours; plugged	Lm	45.00	1,380.00	62,100.00
	Supply and fix 45 mm Thick flush door; Semi-Solid core; Mahogany veneer facing to both sides; hardwood lipped edges to BS 459;				
G	Overall size 900 x 2400mm high	No	4.00	10,523.52	42,094.08
H	Overall size 800 x 2400mm high	No	2.00	9,354.24	18,708.48
	Carried to collection				**317,302.56**

Item	Description	Unit	Qty	Rate	Amount
	Supply and fix the following ironmongery as per "union" or other equal and approved with matching screws:-				
A	Stainless steel ball bearing hinges	Prs	10.00	1,050.00	10,500.00
B	Stainless steel handle	No	6.00	2,060.00	12,360.00
C	3- lever mortice dead lock	No	4.00	3,780.00	15,120.00
D	2- lever mortice dead lock	No	2.00	2,730.00	5,460.00
	Prepare and apply three coats polyurethane clear polish to woodwork				
E	General timber surfaces	Sm	25.00	370.00	9,250.00
F	Surfaces over 225mm but not exceeding 300mm girth	Lm	45.00	160.00	7,200.00
G	Surfaces over 75mm but not exceeding 150mm girth	Lm	6.00	120.00	720.00
	Prepare and apply three coats; primer coat and two coats				
H	General metal surfaces	Sm	30.00	370.00	11,100.00
	Carried to Collection				**71,710.00**
	COLLECTION				
	From Page 2/14				317,302.56
	From Page 2/15 above				71,710.00
	ELEMENT NO. 8 DOORS **Carried to Main Summary**				**389,012.56**

Item	Description	Unit	Qty	Rate	Amount
	SECTION 2 - MAIN HOUSE				
	ELEMENT NO. 9				
	JOINERY FITTINGS				
	Plinths				
	The following in mass concrete class 15				
A	100mm Thick benching	Sm	10.00	1,000.00	10,000.00
	Sawn formwork ; fairfaced to				
B	Edges of plinth exceeding 75mm girth but not exceeding 150mm girth	Lm	17.00	120.00	2,040.00
	Mirrors				
	8mm thick polished plate glass mirror grade A; onto 6mm thick celotex backing;				
C	Mirror size 600 x 900 mm high-washrooms	No	3	3,500.00	10,500.00
	Kichens and Wardrobes				
	Note: All joinery shall be in Timsales boards or from approved equivalent supplier				
	Wardrobes				
D	Wardrobe overall size 4000mm (l) x 600mm (d) x 2400mm (h) comprising 5no equal swing doors pannel in 18mm laminated mdf board to achieve 'brookhil' finish each size 450mm x 2400mm high and finished with edge lipping to Architect's approval and 3mm back veneer; sides, partitions and shelves comprising of laminated 18mm mdf board and 6no drawers size 440mm x 600mm x 250mm high; shoe rack all complete with 20mm Oval chrome plated hanging rail with fixing screws, polished mirror on two swing door panel size 350x1500mm high, soft close runners, approved Soft close malpha hinges, approved Handles (refer to attached render) all in stainless steel finish and all other fixing accessories and as per attached Architect's drawing on.-Proposed master Bedroom 1 Design	No	1	96,768.00	96,768.00
	Carried to collection				**119,308.00**

Item	Description	Unit	Qty	Rate	Amount
A	Wardrobe overall size 2400mm (l) x 600mm (d) x 2400mm (h) comprising 5no equal swing doors pannel in 18mm laminated mdf board to achieve 'brookhil' finish each size 450mm x 2400mm high and finished with edge lipping to Architect's approval and 3mm back veneer; sides, partitions and shelves comprising of laminated 18mm mdf board and 6no drawers size 440mm x 600mm x 250mm high; shoe rack all complete with 20mm Oval chrome plated hanging rail with fixing screws, polished mirror on two swing door panel size 350x1500mm high, soft close runners, approved Soft close malpha hinges, approved Handles (refer to attached render) all in stainless steel finish and all other fixing accessories and as per attached Architect's drawing on.-Proposed Bedroom 2 Design	No	1	58,060.80	58,060.80
B	Wardrobe overall size 1800mm (l) x 600mm (d) x 2400mm (h) comprising 4no equal swing doors pannel in 18mm laminated mdf board to achieve 'brookhil' finish each size 450mm x 2400mm high and finished with edge lipping to Architect's approval and 3mm back veneer; sides, partitions and shelves comprising of laminated 18mm mdf board and 6no drawers size 440mm x 600mm x 250mm high; shoe rack all complete with 20mm Oval chrome plated hanging rail with fixing screws, polished mirror on two swing door panel size 350x1500mm high, soft close runners, approved Soft close malpha hinges, approved Handles (refer to attached render) all in stainless steel finish and all other fixing accessories and as per attached Architect's drawing on.-Proposed Bedroom 3 design	No	1	43,545.60	43,545.60
	Kitchen cabinetry *Supply, assemble and fix the following low level cabinet in kitchen.*				
C	Low level kitchen cabinets overall size 5000mm (l) x 600mm (w) x 900mm high comprising of 6no doors size 450 x 870mm high in 18mm thick laminated mdf board in light grey finish with edge lipping to Arch's approval and drawers size average 650 x 600 x 200mm high; partitions, bottom board shelving in 18mm thick laminated mdf board, 3mm thick veneer backing; with and including matt black handles, malpha hinges, Ball bearing soft close runners and all other necessary fixing accessories.	No	1	42,750.00	42,750.00
	Carried to collection				**144,356.40**

Item	Description	Unit	Qty	Rate	Amount
	Supply, assemble and fix the following high level cabinet in kitchen.				
A	High level kitchen cabinets overall size 5000mm (l) x 300mm (w) x 1050mm high comprising of 3 no doors size 450 x 1050mm high, in 18mm thick laminated mdf board in light grey finish with edge lipping to Arch's approval; partitions, bottom board shelving in 18mm thick laminated mdf board; with and including matt black handles, malpha hinges and any other necessary fixing accessories- Elevation 1		1	38,250.00	38,250.00
	Granite counter top				
B	18mm white granite as "Tiger black" from 'MERU TIMBER' Stores or equal and approved	Sm	3.00	12,500.00	37,500.00
	Carried to collection				**75,750.00**
	COLLECTION				
	From Page 2/16				119,308.00
	From Page 2/17				144,356.40
	From Page 2/18 above				75,750.00
	ELEMENT NO. 9 JOINERY FITTINGS **Carried to Main Summary**				**339,414.40**

Item	Description	Unit	Qty	Rate	Amount
	SECTION 3 - MAIN HOUSE				
	ELEMENT NO. 10				
	ELECTRICAL INSTALLATIONS				
	Supply, Install, connect and set to work the following items:				
A	Lighting points with 1.5mm2x 3-core colour-coded PVC Single (Cu) cables drawn in HG concealed PVC conduits, complete with draw boxes, switch boxes and other necessary accessories.	No	15.00	650.00	9,750.00
B	Ditto as above, but for Switch outlets/boxes	No	15.00	650.00	9,750.00
	Supply, Install, connect and set to work the following items:				
C	Socket outlet points/boxes in Ring Main circuits wired in 3 x 2.5mm2 PVC/SC copper cables drawn in 25mm Ø concealed in HG PVC conduits including all conduit and fittings accessories.	No	15.00	2,100.00	31,500.00
D	20A DP outlet in HG rigid PVC conduit, with circuits of 3x2.5 mm2 PVC single cables complete with draw boxes, switch boxes and other necessary accessories.	No	2.00	1,260.00	2,520.00
E	45A Cooker control unit in HG rigid PVC conduit with wiring of 3x6mm2 PVC single cables ,complete with draw boxes, switch boxes and other necessary accessories.	No	1.00	2,100.00	2,100.00
	Distribution Board				
F	6 -Way TPN Distribution Board complete with MCBs.	No	1.00	15,000.00	15,000.00
G	300x250x120 adaptor box	No	1.00	1,340.00	1,340.00
	Carried to collection				**71,960.00**

Item	Description	Unit	Qty	Rate	Amount
	Supply and Fix the following in Electrical fittings & Accessories:				
	Lighting Fittings				
	Switch Plates as follows:				
A	1 gang, 2 way -5A	No	10.00	295.00	2,950.00
B	2 gang, 2 way -5A	No	5.00	670.00	3,350.00
	Power Fittings				
	Finish Switch Plates as follows:				
C	13A Twin Socket Plate.	No	14.00	800.00	11,200.00
D	13A Twin Waterproof Socket Plate.	No	1.00	1,765.00	1,765.00
E	20A DP Switch Plate, VIP Gold with neon indicator	No	1.00	840.00	840.00
F	45A Ordinary Finish Cooker Control Unit with 13A Single Socket	No	1.00	1,840.00	1,840.00
G	Ordinary Finish Cooker connector	No	1.00	800.00	800.00
	Other Fittings				
H	Bell Push Switch	No	1.00	1,200.00	1,200.00
I	Bell Anchor Ding Dong	No	1.00	1,500.00	1,500.00
J	Brass Finish TV Outlet Plates	No	1.00	1,765.00	1,765.00
	Light Fittings				
K	LED light fitting as "Energy Saver" ceiling mounted-Contractor to provide sample for approval by Client.	No	15.00	950.00	14,250.00
	Carried to collection				**41,460.00**
	COLLECTION				
	From Page 2/19				71,960.00
	From Page 2/20 above				41,460.00
	ELEMENT NO. 10 ELECTRICAL INSTALLATIONS **Carried to Main Summary**				**113,420.00**

Item	Description	Unit	Qty	Rate	Amount
	SECTION 3 - MAIN HOUSE				
	ELEMENT NO 11				
	PLUMBING INSTALLATIONS				
	Plumbing and drainage points.				
A	WC Points	No	3.00	2,220.00	6,660.00
B	WHB Points	No	4.00	2,220.00	8,880.00
C	Shower Points	No	3.00	2,220.00	6,660.00
D	Floor Trap Points	No	6.00	2,220.00	13,320.00
E	Kitchen Sink Points	No	1.00	2,220.00	2,220.00
	Take delivery and fix only the following sanitary fittings				
F	Ceramic water closet comprising pan, heavy duty plastic seat & cover, concealed cistern, and all other accessories including flush pipe and trap	No	4.00	12,500.00	50,000.00
G	Shower Mixer	No	3.00	4,500.00	13,500.00
H	Kitchen sink and waste	No	1.00	11,680.00	11,680.00
I	3-Way Concealed Showerhead complete with chrome plated mixtaps & flexible connection	No	3.00	10,000.00	30,000.00
J	Wash Basin with pedestal, basin tap, and waste	No	4.00	7,140.00	28,560.00
K	Toilet Roll Holder	No	4.00	2,940.00	11,760.00
L	Soap Holder	No	3.00	2,940.00	8,820.00
M	Towel Rail	No	3.00	2,100.00	6,300.00
N	Towel Ring	No	1.00	1,260.00	1,260.00
P	Supply and install 5000Lts over head watertank as 'Roto' or approved equivalent.	No	1.00	54,600.00	54,600.00
	ELEMENT NO. 11 PLUMBING INSTALLATIONS **Carried to Main Summary**				**254,220.00**

Item	Description	Unit	Qty	Rate	Amount
	SECTION 2 - MAIN HOUSE				
	MAIN SUMMARY		Page		
1	Substructures		2/3		1,466,800.00
2	Reinforced Concrete Frame		2/4		269,600.00
3	Walling		2/5		396,800.00
4	Roof Construction and Finishes		2/7		1,324,790.00
5	External Finishes		2/10		297,510.00
6	Internal Finishes		2/11		1,072,110.00
7	Windows		2/13		395,230.80
8	Doors		2/15		389,012.56
9	Joinery fittings		2/18		339,414.40
10	Electrical Installations		2/20		113,420.00
11	Plumbing Installations		2/21		254,220.00
	SECTION NO. 3 TOTAL AMOUNT CARRIED TO THE GRAND SUMMARY				**6,318,907.76**

Item	Description	Unit	Qty	Rate	Amount
	SECTION NO 3 - EXTERNAL WORKS				
	ELEMENT NO 1 : FOUL WATER DRAINAGE (ALL PROVISIONAL)				
	Excavations including trimming sides and bottoms of excavations; maintaining and supporting sides; and keeping free from water, mud and fallen material; with and including destruction of termites nests within site of works,take out and destroy queens, impregnate holes and tunnels with insecticide and fill voids with approved material				
	Excavations including maintaining and supporting sides and keeping free from water mud and fallen material				
A	Trench, average 1000mm, deep for 150mm diameter pipe	Lm	15	165	2,475.00
B	Ditto for 100 mm diameter pipe	Lm	10	165	1,650.00
	Key terrain or other equal and approved buried waste and soil UPVC pipes and fittings.				
C	150 mm Diameter soil pipe laid in trench	Lm	15	1,180	17,700.00
D	100mm Diameter soil pipe laid in trench	Lm	10	1,000	10,000.00
	Plain concrete 1:3:6 (25mm aggregates) as described in				
E	150 mm Thick surround including haunching to 150mm diameter pipes	Lm	15	210	3,150.00
F	150mm Thick surround including haunching to 100mm diameter pipes	Lm	10	210	2,100.00
	The following in inspection chambers				
G	Manhole internal size 600 x 450mm to depth not exceeding 1.50m deep, comprising of plain concrete (1:3:6) in 150mm thick slab, 250 thick benching 150mm thick concrete block walling, water-proof screeds to sides and bottoms, with recessed top to receive heavy duty cover including all necessary excavations, disposal, formwork and reinforcement	No	5	12,000	60,000.00
H	Medium duty fibre manhole cover size 600 x 450	No	5	4,200	21,000.00
	ELEMENT NO 1 FOUL WATER DRAINAGE **Carried to Main Summary**				**118,075.00**

Item	Description	Unit	Qty	Rate	Amount
	SECTION NO 3 - EXTERNAL WORKS				
	External Works summary		Page		
1	Foul Drainage		3/1		118,075.00
	SECTION NO.5 TOTAL AMOUNT CARRIED TO THE GRAND SUMMARY				**118,075.00**

Item	Description	Unit	Qty	Rate	Amount
	SECTION NO. 4 - PROVISIONAL SUMS				
	Provisional				
A	Provide a provisional sum of **Kshs 130,000.00 for** bio digester	Item			130,000.00
	SECTION NO. 4 **Carried to**				
	M&E Installations **Grand summary**			**KSHS**	**130,000.00**

PROPOSED RESIDENTIAL HOUSE ON PLOT LR NO

FOR

JEREMIAH MUSOMBA MUINDE

	GRAND SUMMARY	SECTION	AMOUNT
1	MAIN HOUSE	2	6,318,907.76
2	EXTERNAL WORKS	3	118,075.00
	TOTAL BUILDERS WORK		6,436,982.76
3	PRIME COST AND PROVISIONAL SUMS	4	130,000.00
			6,566,982.76
	TOTAL AMOUNT CARRIED TO FORM OF TENDER INC VAT	KSHS.	6,566,982.76

SIGNED:
(CONTRACTOR) .....

Address: .....

Tel No: .....

Date: .....

SIGNED:
(EMPLOYER) .....

Address: .....

Tel No: .....

Date: .....